PROJECT NOTE

TO: Project File

SUBJECT: Jard Company, Inc.

TASK DESCRIPTION: Monitoring Well Elevation Data Evaluations

TDD NO.: 13-09-0001

W.O. NO.: 20114-091-998-0904

TASK NO.: 60

DATE: 30 September 2013

PREPARED BY: Carolyn Imbres

Evaluation of ground water monitoring well screened intervals:

Data was evaluated from several sources to determine the depths, adjusted to mean sea level (msl), of the screened intervals of ground water monitoring wells presented in the Jard Company Inc. Hazard Ranking System (HRS)/National Priorities List (NPL) Documentation Record. These data sources include elevation surveys, boring logs, and cross-sections produced as part of previous investigations of the Jard Company Inc. property. The relevant sections of the HRS references used to support this Project Note are included as Attachment A. The monitoring wells presented in the HRS/NPL Documentation Record include the following: background wells EPA-100, EPA-107, and MW-11; and contaminated wells MW-3, MW-3D, MW-6, and MW-9D.

The msl depths of the screened intervals of the HRS groundwater monitoring wells were determined using the well construction boring log records, which documented these intervals in depths below ground surface (bgs) [36, pp. 41, 43; 65, pp. 69, 72, 78; 88, pp. 145, 161]. Elevations of well casings and the ground surface at each well, as referenced to an arbitrary elevation point of 100 feet (Columns A and B below), were obtained from an elevation survey performed during investigations for the Kocher Drive and Park Street sites and were included in correspondence from Vermont Department of Environmental Conservation (VT DEC) representative Patricia Coppolino [52]. Data from a second elevation survey which presented top of casing msl elevations were evaluated for several wells, and where necessary were evaluated in conjunction with the Kocher Drive and Park Street sites survey [68, p. 7]. Once the msl ground surface elevation of a monitoring well was determined based on data provided from one or both of the elevation surveys, the top and bottom of the screened interval (in feet bgs) was subtracted from the ground surface elevation, to calculate the screened well interval in depth above msl.

Well ID	Inner Casing Elevation (feet) (A)	Ground surface elevation (feet) (B)	A – B = C (feet)	Top of Casing Elevation (msl) (D)	Ground surface elevation (msl)	Screened Interval (feet bgs)	Screened Interval (msl)	References
					D - C =			52, p. 3; 68, p.
EPA-100	145.15	142.42	2.73^{1}	683.06	680.33	27-32	653.33-648.33	7; 88, p. 146
					D-C=			52, p. 2; 68, p.
EPA-107	114.89	115.07^2	-0.18	650.01	650.19	12.2-22.2	637.99-627.99	7; 88, p. 162
								53, p. 1; 65, pp.
MW-11				667.23	667.46^3	1.5-11.5	665.96-655.96	44, 69; 68, p. 7

	Inner Casing	Ground surface	A D	Top of Casing	Ground surface	Screened	Screened	
Well ID	Elevation (feet) (A)	elevation (feet) (B)	A - B = $C (feet)$	Elevation (msl) (D)	elevation (msl)	Interval (feet bgs)	Interval (msl)	References
7,022	(1000) (11)	(1000) (2)	G (1888)	(11101) (2)	(2222)	(1000 250)	(11151)	36, p. 41; 53, p.
					D - C =			1; 65, p. 44; 68,
MW-3			2.2^{4}	685.75	683.55	2.5-8.5	681.05-675.05	p. 7
								36, p. 43; 53, p.
					_			1; 65, pp. 44,
MW-3D				686.29	683.55 ⁶	23-28	660.55-655.55	54, 72; 68, p. 7
					D - C =			53, p. 1; 65, p.
MW-6			2.5^{5}	682.64	680.14	6.8-11.8	673.34-668.34	44; 68, p. 7
								53, p. 1; 65, pp.
MW-9D				669.34	669.62 ⁷	22-27	647.62-642.62	44, 78; 68, p. 7

¹ The inner casing (PVC riser) was documented during well installation as measuring 2.7 feet above ground surface (ags) [88, p. 146].

² The road box was documented during well installation as flush with the ground surface [88, p. 162].

^{4,5} The distance between the top of the inner casing and the ground surface was documented during well installation [36, pp. 41, 43].

Evaluation of ground water flow direction:

The direction of ground water flow within the overburden aquifer beneath and downgradient of the Jard Company Inc. property was evaluated based on depth to ground water measurements collected from 20 ground water monitoring wells as part of the EPA Site Reassessment (SR) [see HRS Reference 10, pp. 10-11]. On 27 March 2013, WESTON personnel measured the depth to ground water in feet from the top of casing (TOC) at ground water monitoring well locations associated with the Jard Company Inc. (Jard) site [10, pp. 10-11]. WESTON also documented the geographic location of the monitoring wells using a Global Positioning System (GPS) unit [10, p. 52]. The Johnson Company provided survey data indicating the TOC elevations for the monitoring wells in feet above msl [68, p.7]. The depths to ground water were then subtracted from the TOC elevations to determine depths to ground water in feet above msl, and these data points were plotted and contoured using Surfer 8. Based on mapped contours and ground water elevation data, ground water flow beneath and downgradient of the Jard Company Inc. property is generally to the northwest (see Attachment C).

2

^{3,7} The monitoring well metal casing was documented to be flush with the ground surface [53, p. 1; 65, pp. 69, 78].

⁶ The ground surface elevation was not available for this well location in available documentation. In addition, the distance between ground surface and the top of casing was not indicated on available boring logs. Based on observations made in the field by Weston Solutions, Inc. personnel during the April 2013 Site Reassessment (see photograph in Attachment B), and documentation provided in a Johnson Company cross-section (Ref. 65, p. 54), the ground surface elevation of MW-3D is similar to that of nearby well MW-3. Therefore, the ground surface elevation documented for MW-3 is also used for MW-3D.

ATTACHMENT A - REFERENCES

HRS Reference No. 36 (Excerpt): Wehran EnviroTech. 1991. Phase 2 Environmental Site Assessment, Jard Company Property, Bennington, Vermont. February.


HRS Reference No. 52: Correspondence regarding Elevation Survey. Email with Attachment, from Coppolino, P., Vermont Agency of Natural Resources to Hornok, G. Weston Solutions, Inc., (START). 16 September 2013.

HRS Reference No. 53: Guntlow & Associates, Inc. Monitoring Well Elevation Survey Data. Internet Accessed on 30 September 2013 from: ftp://ftp.anr.state.vt.us/. Data generated on behalf of The Johnson Company (see HRS Reference No. 65, p. 25).

HRS Reference No. 65 (Excerpt): The Johnson Company. 2010. Limited Phase II Environmental Site Assessment Report: Stage I, Former Jard Company Site, Bennington, Vermont. 3 December.


HRS Reference No. 68 (Excerpt): The Johnson Company. 2013. October 2012 Groundwater Sampling, Former Jard Company Site. 25 February.

HRS Reference No. 88 (Excerpt): Weston Solutions, Inc. 2013. Removal Program Preliminary Assessment/Site Investigation Report Addendum for the Park Street Site, Bennington, Bennington County, Vermont, July, August, and September 2012. TDD No. 01-12-03-0002. March.



HRS Reference #36 HRS Reference #54

Page 41 of 149 Page 4 of 24



Imbres, Carolyn

From: Hornok, Gerald

Sent: Monday, September 16, 2013 1:13 PM

To: Imbres, Carolyn Subject: FW: Survey

Attachments: KocherPark St GW Elevation surveysheet.pdf

From: Coppolino, Patricia [mailto:Patricia.Coppolino@state.vt.us]

Sent: Monday, September 16, 2013 1:01 PM

To: Hornok, Gerald

Cc: Bosworth, Martha (bosworth.martha@epa.gov)

Subject: Survey

Trish Coppolino, Brownfields Program Manager p. 802.249.5822

1 National Life Drive – Davis 1 Montpelier, VT 05620-3704

http://www.anr.state.vt.us/dec/wastediv/SMS/brownfields-home.htm

HRS Reference #52 Page 1 of 4

Kocher Drive and Park Street Groundwater Elevation Survey

Elevation	Back site	Instrument Height	Forward site	Elevation	Station/Flag Description
100.00	0.00	100.00		vation of 100 feet	Instrument Height at Location 1 - Kocher Drive
	0.00	100.00	6.50	93.50	EPA MW-03 Road Box
	0.00	100.00	6.83	93.17	EPA MW-03 Inner Casing
	0.00	100.00	7.08	92.92	EPA MW-02 Ground Surface
	0.00	100.00	4.23	95.77	EPA MW-02 Inner Casing
	0.00	100.00	6.29	93.71	EPA MW-01 Road Box
	0.00	100.00	6.51	93.49	EPA MW-01 Inner Casing
	0.00	100.00	1.97	98.03	Ground Surface NW Corner Fence Post of Propane Enclosure
98.03	13.27	111.30	Back Site on C	S at Propane Encl.	New Instrument Height at entrance to soccer field driveway
	0.00	111.30	6.67	104.63	Ground Surface at chain-link fence post at NE corner of car dealership
	0.00	111.30	0.36	110.94	Ground Surface elevation at third rock west on entrance to soccer field
110.94	7.62	118.56	Back Site	on GS at Rock	New Instrument Height at center of soccer field driveway
	0.00	118.56	11.90	106.66	EPA MW-04 Road Box Ground Surface
100.00	0.00	118.56	9.55	109.01	EPA MW-04 Inner Casing
104.63	5.56	110.19	0.00	0.00	New Instrument Height along Progress Way
	0.00	110.19	3.28	106.91	Ground Surface at Stop sign corner of Progress Way and Kocher Drive
106.91	5.72	112.63	Back Site	on Stop Sign	New Instrument Height at location along Kocher outside Kaman
	0.00	112.63	1.25	111.38	Ground Surface at concrete slab outside of Kaman Industries
111.38	3.70	115.08	Back Site of	on concrete slab	New Instrument Height at location along Kocher near fire hydrant
	0.00	115.08	0.10	114.98	Ground Surface at Telephone Pole No. 211, 11, 2 along N. Branch Street
	0.00	115.08	4.18	110.90	Stormwater Grate at the corner of Park Street and Kocher Drive
114.98	7.51	122.49	Back Site on	Telephone Pole	New Instrument Height at front yard of 1086 N. Branch St.
	0.00	122.49	7.42	115.07	EPA-107 Road Box at surface
	0.00	122.49	7.60	114.89	EPA-107 Inner Casing
110.90	6.88	117.78	Back Site	on Storm Grate	New Instrument Height at location along Park Street

HRS Reference #52 R:\12030002\Kocher&Park St. GW Elevation surveysheet.xlsx

Page 2 of 4

Kocher Drive and Park Street Groundwater Elevation Survey

Elevation	Back site	Instrument Height	Forward site	Elevation	Station/Flag Description
	0.00	117.78	2.40	115.38	Ground Surface at Telephone Pole No. 20A/36A along Park Street
115.38	5.98	121.36	Back Site on	Telephone Pole	New Instrument Height at location adjacent to EPA-106S/106D
	0.00	121.36	5.29	116.07	EPA-106S Concrete Road Box
	0.00	121.36	2.78	118.58	EPA-106S Inner Casing
	0.00	121.36	5.44	115.92	EPA-106D Concrete Road Box
	0.00	121.36	3.08	118.28	EPA-106D Inner Casing
	0.00	121.36	3.08	118.28	Steel Plate (Neenah, Inc.) at corner of Bowen Road and Park Street
118.28	10.78	129.06	Back site	on Steel Plate	New Instrument Height at location south lawn of Plesan Facility
	0.00	129.06	2.65	126.41	EPA-108S Ground Surface
	0.00	129.06	0.27	128.79	EPA-108S Inner Casing
	0.00	129.06	1.70	127.36	EPA-108D Ground Surface
	0.00	129.06	0.18	128.88	EPA-108D Inner Casing
	0.00	129.06	4.25	124.81	Neenah Foundry Drain in south lawn of Plesan Facility
124.81	12.30	137.11	Back site or	n Neenah Drain	New Instrument Height at Balustrades of Plesan Facility SW of Other
	0.00	137.11	4.63	132.48	MW-08 Ground Surface Actual Elevation = 670.60
	0.00	137.11	0.00	137.11	Corner of pavement at Bowen Road and Plesan SE loading dock
137.11	11.88	148.99	Back site on C	Corner of pavement	New Instrument Height at Entrance to Former Jard facility
	0.00	148.99	6.57	142.42	EPA-100 Ground Surface
	0.00	148.99	3.84	145.15	EPA-100 Inner Casing
	0.00	148.99	5.25	143.74	MW-4D on Former Jard facility
118.28	7.94	126.22	Back site	on Steel Plate	New Instrument Height at front yard of XX Park Street
	0.00	126.22	0.98	125.24	Ground Surface at Telephone No. XX on Park Street
	0.00	126.22	9.45	116.77	EPA-104D Ground Surface
	0.00	126.22	6.78	119.44	EPA-104D Inner Casing
	0.00	126.22	9.38	116.84	EPA-104S Ground Surface
	0.00	126.22	6.50	119.72	EPA-104S Inner Casing
125.24	13.86	139.10	Back site on	Telephone Pole	New Instrument Height at Corner of bridge over the Waloomsac
	0.00	139.10	8.71	130.39	EPA-101 Ground Surface
	0.00	139.10	8.94	130.16	EPA-101 Inner Casing
	0.00	139.10	5.49	133.61	Intermediate point along path northwest of bridge
133.61	2.15	135.76	Back site on l	Intermediate point	New Instrument Height along path northwest of bridge
	0.00	135.76	14.34	121.42	EPA-102 Ground Surface
	0.00	135.76	11.85	123.91	EPA-102 Inner Casing
121.42	1.75	123.17	Back site o	n EPA-102 GS	New Instrument Height along path between EPA-102 and EPA-103
	0.00	123.17	6.93	116.24	Intermediate point along path between EPA-102 and EPA-103
116.24	3.78	120.02		Intermediate point	New Instrument Height along path between EPA-102 and EPA-103
	0.00	120.02	4.65	115.37	EPA-103 Ground Surface
	0.00	120.02	2.37	117.65	EPA-103 Inner Casing

HRS Reference #52 R:\12030002\Kocher&Park St. GW Elevation surveysheet.xlsx

Kocher Drive and Park Street Groundwater Elevation Survey

FI 41	D 1 1/	T (177.14	T 1.4	T1 41	
Elevation	Back site	Instrument Height	Forward site	Elevation	Station/Flag Description
115.37	8.25	123.62	Back site on EPA-103 GS		New Instrument Height south of EPA-103
	0.00	123.62	13.42	110.20	Intermediate point along path northwest of EPA-103
110.20	4.05	114.25	Back site on l	ntermediate point	New Instrument Height north of Intermediate point
	0.00	114.25	7.09	107.16	Intermediate point along path north of Intermediate point
107.16	5.43	112.59	Back site on l	ntermediate point	New Instrument Height north of Intermediate point
	0.00	112.59	3.68	108.91	EPA-105 Ground Surface
	0.00	112.59	0.93	111.66	EPA-105 Inner Casing

Page 9 of 24

Table 3 Potentiometric Data Former Jard Company Site Bennington, Vermont


T	Top of Casing	7/29	9/2010	8/	6/2010	8/3	0/2010
Location	Elevation (ft.) (1)	DTW (ft.)	Elevation (ft.)	DTW (ft.)	Elevation (ft.)	DTW (ft.)	Elevation (ft.)
EPA-2	684.40	Dry	< 679.70	Dry	< 679.70	Dry	< 679.70
EPA-3	687.11	9.56	677.55	9.11	678.00	10.06	677.05
EPA-4	685.88	8.80	677.08	8.44	677.44	9.24	676.64
EPA-5	686.01	inace	cessible	inac	cessible	des	troyed
EPA-6	683.72	21.74	not available (3)	21.31	not available (3)	9.36	674.36
EPA-7	683.15	inace	cessible	inac	cessible	10.87	672.28
EPA-8	678.50	inace	cessible	inac	cessible	8.05	670.45
EPA-9	683.91	Dry	< 672.39	10.97	672.94	Dry	< 672.39
EPA-10	684.23	10.34	673.89	10.00	674.23	10.76	673.47
MW-1	680.05	9.26	670.79	9.05	671.00	9.80	670.25
MW-2	684.68	7.44	677.24	6.91	677.77	8.06	676.62
MW-3	685.75	8.78	676.97	not me	easured (2)	9.37	676.38
MW-3D	686.29	not con	nstructed	9.69	676.60	10.57	675.72
MW-4	683.94	7.50	676.44	7.05	676.89	8.20	675.74
MW-4D	683.91	not con	nstructed	8.46	675.45	9.51	674.40
MW-6	682.64	11.17	671.47	11.07	671.57	11.87	670.77
MW-6D	682.82	not con	nstructed	11.52	671.30	12.29	670.53
MW-7	670.53	not con	nstructed	3.91	666.62	4.77	665.76
MW-8	670.60	not con	nstructed	5.26	665.34	5.86	664.74
MW-9	669.43	not con	nstructed	not co	onstructed	4.69	664.74
MW-9D	669.34	not con	nstructed	not co	onstructed	5.12	664.22
MW-10	666.91	not con	nstructed	2.15	664.76	2.66	664.25
MW-11	667.23	not con	nstructed	1.51	665.72	1.96	665.27
MW-12	670.05	not con	nstructed	4.08	665.97	4.35	665.70
MW-13	664.03	not con	nstructed	5.61	658.42	5.70	658.33
PZ-01	687.75	2.68	685.07	1.92	685.83	4.32	683.43
PZ-02	not measured (4)	not con	nstructed	2.14	not available (4)	des	troyed
PZ-03	678.20	2.83	675.37	2.59	675.61	3.58	674.62
PZ-04	664.06	2.97	661.09	2.44	661.62	3.40	660.66
PZ-05	661.25	2.43	658.82	2.03	659.22	2.73	658.52
PZ-06	654.28	3.28	651.00	2.85	651.43	3.69	650.59
PZ-12	666.95	not con	nstructed	2.52	664.43	2.87	664.08
PZ-13	657.20	not con	nstructed	0.98	656.22	1.01	656.19
PZ-14	660.69	not co	nstructed	not co	onstructed	2.13	658.56


¹⁾ Surveyed by Guntlow & Associates, Inc. licensed surveyor

²⁾ Not measured due to suspected potential for presence of non-aqueous phase liquid (NAPL).

³⁾ Elevation not available due to change in top-of casing elevation between time of measurement and time of survey.

⁴⁾ Elevation not available; location destroyed prior to survey.





MW-11

Project: JARD Site Location: Bennington, VT Job #: 3-2218-3

Geologist: DPB TOC Elevation: 667.23

PID Depth Well Construction Description Geology (ft. bgs) **Diagram** (ppm) 0.00 Flushmount Gravelly SAND, some silt, humid, dark brown, organic. 2" PVC Casing Cetco Bentonite COBBLES and silty sand, cobbles generally rounded, up to $0.4\mbox{'}\mbox{in}$ diameter. Silty sand is cohesive, very dark brown except red-orange from 1.3 to 1.5 fbgs. Damp. Chips 0.5 No Recovery. 5.00 Screen COBBLES with gravelly sand. Cobbles are rounded, gravel is angular. Sand is very fine to coarse, well graded. Saturated. Filpro Silica Filtation Sand 0.4 No Recovery. 10.00 Same as 5-7' bgs, except cobbles are subangular to angular. **Bottom Cap** Filpro Silica 0.5 Filtation Sand No Recovery.

> Native Material Caving

Drilling Date: 08/04/10
Drilling Company: Boart Longyear
Drilling Method: Rotosonic

Easting (VT SPCS): 443592.11 **Northing (VT SPCS):** 43666.868


15.00

Construction Materials

Casing: Schedule 40 PVC Screen: PVC with 0.010 slot Filter Pack: #0 Filter Sand

Seal: Bentonite Surface Completion: --

Riser Pipe and Screen Diameter: 2.0"




MW-3D

Project: JARD Site Location: Bennington, VT Job #: 3-2218-3

Geologist: DPB **TOC Elevation: 686.29**

Depth (ft. bgs)	PID (ppm)	Well Construction Diagram	Geology	Description
— 0.00	0	Stickup	Recentation and the second	



Drilling Date: 08/02/10 Drilling Company: Boart Longyear Drilling Method: Rotosonic


Easting (VT SPCS):443680.58 **Northing (VT SPCS):** 43429.918

Construction Materials

Casing: Schedule 40 PVC Screen: PVC with 0.010 slot Filter Pack: #0 Filter Sand

Seal: Bentonite Surface Completion: --

Riser Pipe and Screen Diameter: 2.0"



MW-9D

Project: JARD Site Location: Bennington, VT Job #: 3-2218-3

Geologist: DPB TOC Elevation: 669.34

PID Depth **Well Construction Geology Description** (ft. bgs) (ppm) **Diagram** 0.00 Flushmount Gravelly SAND, some silt, humid, dark brown, organic. Very fine SAND, some silt, humid, red-orange Same as above, but very light brown. COBBLES with silty sand, damp, silty sand is very dark brown. Tree roots. Gravelly COBBLES, damp, some fine to medium sand, trace silt. Cobbles are rounded to subangular. 5.00 0.7 No Recovery. Cetco Bentonite Chips 10.00 COBBLES with gravel and sand, wet. Sand is fine to coarse, gravel is fine to coarse. Cobbles and gravel are subangular to angular. 2" PVC Casing Same as above, but lacking fine to medium gravel. 0.5 No Recovery. 15.00 Gravelly SAND, light brown sand is fine to coarse, gravel is fine. Wet, noncohesive. Sandy GRAVEL, gravel is coarse, sand is fine to coarse. Wet, gravel is rounded to subangular. Cobbley SAND, some gravel. Sand is fine to coarse. Brown cobbles 0 are generally rounded, some angular, subangular. Wet. No Recovery. 20.00 Fine SAND, some medium sand and silt, saturated, brown. Gravelly COBBLES, some coarse sand, wet. Cobbles are rounded to subangular, gravel subangular to angular. Filpro Silica Fine to coarse SAND, some fine gravel, fine to medium sand is brown. Gravel is subangular, wet. Filtation Sand 0.1 Fine to medium SAND, few cobbles. Sand is brown. Cobbles rounded. Wet, noncohesive. Screen No Recovery. 25.00 Brown sand, fine to medium at top, increasing coarse sand with depth, Bottom Cap becomes medium to coarse. Wet, noncohesive, 0.5 Filpro Silica Filtation Sand Gravel, fine to coarse, rounded to angular, wet.

Grey-brown silty CLAY, trace fine sand, gravel. Humid, hard.

Durability increasing with depth. Cannot roll 1/2" bead at 29.2 fbgs, Cetco Bentonite Chips 30.00 but can roll <1/8" bead at 30.0 fbgs.

Drilling Date: 08/05/10
Drilling Company: Boart Longyear
Drilling Method: Rotosonic

Easting (VT SPCS): 443546.058 **Northing (VT SPCS):** 43572.481

Construction Materials

Casing: Schedule 40 PVC Screen: PVC with 0.010 slot Filter Pack: #0 Filter Sand

Seal: Bentonite Surface Completion: --

Riser Pipe and Screen Diameter: 2.0"

Table 1 Potentiometric Data Former Jard Company Site Bennington, Vermont

		Top of Casing	7/29	9/2010	8/6	5/2010	8/3	0/2010	4/13	8/2012	10/2	17/2012
Location	Interval	Elevation (ft.) (1)	DTW (ft.)	Elevation (ft.)	DTW (ft.)	Elevation (ft.)						
EPA-3	Shallow	687.11	9.56	677.55	9.11	678.00	10.06	677.05	10.98	676.13	10.40	676.71
EPA-9	Shallow	683.91	Dry	< 672.39	10.97	672.94	Dry	< 672.39	Dry	< 672.39	Dry	< 672.39
EPA-100	Deep	683.06	not con	nstructed	not co	nstructed	· · · · · ·	nstructed	not con	nstructed	9.52	673.54
EPA-101	Deep	665.23	not con	nstructed	not con	nstructed	not co	not constructed		nstructed	7.04	658.19
EPA-102	Deep	658.98	not con	nstructed	not constructed		not constructed		not constructed		6.73	652.25
EPA-103	Deep	652.73	not con	nstructed	not con	not constructed		not constructed		nstructed	8.59	644.14
EPA-104S	Shallow	654.80	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	4.40	650.40
EPA-104D	Deep	654.54	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	4.24	650.30
EPA-105	Deep	646.35	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	7.81	638.54
EPA-106S	Shallow	653.70	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	4.43	649.27
EPA-106D	Deep	653.40	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	4.23	649.17
EPA-107	Deep	650.01	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	2.75	647.26
EPA-108S	Shallow	665.47	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	6.23	659.24
EPA-108D	Deep	665.71	not con	not constructed		nstructed	not co	nstructed	not con	nstructed	6.35	659.36
MW-1	Shallow	680.05	9.26	670.79	9.05	671.00	9.80	670.25	10.60	669.45	9.80	670.25
MW-2	Shallow	684.68	7.44	677.24	6.91	677.77	8.06	676.62	8.77	675.91	8.05	676.63
MW-3	Shallow	685.75	8.78	676.97	not med	asured (2)	9.37	676.38	10.43	675.32	9.82	675.93
MW-3D	Deep	686.29	not con	nstructed	9.69	676.60	10.57	675.72	11.68	674.61	11.00	675.29
MW-4	Shallow	683.94	7.50	676.44	7.05	676.89	8.20	675.74	8.87	675.07	8.12	675.82
MW-4D	Deep	683.91	not con	nstructed	8.46	675.45	9.51	674.40	10.43	673.48	9.50	674.41
MW-6	Shallow	682.64	11.17	671.47	11.07	671.57	11.87	670.77	13.21	669.43	12.31	670.33
MW-6D	Deep	682.82	not con	nstructed	11.52	671.30	12.29	670.53	13.30	669.52	12.46	670.36
MW-8	Shallow	670.60	not coi	nstructed	5.26	665.34	5.86	664.74	6.87	663.73	6.00	664.60
MW-9	Shallow	669.43	not con	nstructed	not con	nstructed	4.69	664.74	5.60	663.83	4.54	664.89
MW-9D	Deep	669.34	not con	nstructed	not con	nstructed	5.12	664.22	6.04	663.30	5.02	664.32
MW-10	Shallow	666.91	not con	nstructed	2.15	664.76	2.66	664.25	3.28	663.63	2.42	664.49
MW-11	Shallow	667.23	not con	nstructed	1.51	665.72	1.96	665.27	2.36	664.87	1.77	665.46
MW-12	Shallow	670.05	not con	nstructed	4.08	665.97	4.35	665.70	4.48	665.57	4.22	665.83
MW-13	Shallow	664.03	not con	nstructed	5.61	658.42	5.70	658.33	6.04	657.99	5.66	658.37
PZ-12	Shallow	666.95	not con	nstructed	2.52	664.43	2.87	664.08	3.70	663.25	2.49	664.46
PZ-13	Shallow	657.20	not con	nstructed	0.98	656.22	1.01	656.19	1.03	656.17	0.98	656.22
PZ-14	Shallow	660.69	not con	nstructed	not con	nstructed	2.13	658.56	2.66	658.03	2.12	658.57
PZ-15	Shallow	662.52	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	1.68	660.84
PZ-16	Shallow	649.51	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	2.14	647.37
PZ-17	Shallow	666.68	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	3.11	663.57
PZ-18	Shallow	654.21	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	3.01	651.20
PZ-19	Shallow	652.74	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	3.88	648.86
PZ-20	Shallow	647.18	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	2.62	644.56
PZ-21	Shallow	645.06		nstructed		nstructed		nstructed		nstructed	2.58	642.48
PZ-101	Shallow	685.87	not constructed			nstructed		nstructed	not con	nstructed	3.01	682.86
PZ-102	Shallow	680.78	not constructed		not con	nstructed	not co	nstructed	not con	nstructed	3.20	677.58
PZ-103	Shallow	not measured (4)	not con	nstructed	not con	nstructed	not co	nstructed	not con	nstructed	2.35	not available (4)
PZ-104	Shallow	666.63		nstructed		nstructed	not constructed		not constructed		3.13	663.50
PZ-105	Shallow	660.27		nstructed		nstructed		nstructed	not constructed		2.31	657.96
PZ-106	Shallow	650.85		nstructed		nstructed		nstructed	not con	nstructed	2.31	648.54
PZ-107	Shallow	644.07		nstructed		nstructed		nstructed		nstructed	1.45	642.62

¹⁾ Surveyed by Guntlow & Associates, Inc.; Weston Solutions, Inc.; and The Johnson Company, Inc.

Page 15 of 24

²⁾ Not measured due to suspected potential for presence of non-aqueous phase liquid (NAPL).

³⁾ Elevation not available due to change in top-of casing elevation between time of measurement and time of survey.

⁴⁾ Elevation not available; location destroyed prior to survey.

	on Solutio	,		Doul: Ct			OMPLETION LOG		age 1 of 2
Project				Park Stre		Boring ID Well ID	NA	Groundwa	
Locatio					ton, Vermont		EPA-100	Date	Depth (ft)
Date D				28-Aug-1		Drilling Method	ODEX and Drive and Wash	30-Aug-12	9.30
	Company					Sampling Method	2-in diam. Split Spoon		
	Foreman				W. Thompson	Completion Depth	32 feet bgs		
Drill Ri				CME-550		Surface Elevation	A	/CTADI	
Logged	Well	Cwlit	ı	George	viavris - weston, :	Supertuna Technicai	Assessment and Response T	eam (START)
Depth (ft bgs)	Construct.	Split Spoon No.	Blow Counts (N)	Recovery (inches)		Soil Des	cription		ative Density Descriptor
					0 - 6" <i>-</i> Topsoil				
2					Boring advanced 33 drive and wash drilli	and then			
_ 4					_	_	casing was advanced while using c split spoons and 140 lb. auto-hamn		
- 6	∇				Water table at 6.61 t	feet bgs.			
8					0 - 33 foot Gravel	copples and boulders (w	hite, pink, tan, buff, and black qua	rtzite and	
10		NA	NA	NA		ragments), and fine-to-co		rizhte dila	NA
12									
14									
16									
18									
20									
22									
- 24									
- 26									

Westo	n Solution	ns, Inc).		SOIL BO	RING/WELL CO	MPLETION LOG	F	Page 2 of 2
Project	:			Park Stre	eet Site	Boring ID	NA	Groundwa	ater Levels*
Locatio	n			Benningt	ton, Vermont	Well ID	EPA-100	Date	Depth (ft)
Date D	rilled			28-Aug-1	12	Drilling Method	ODEX and Drive and Wash	30-Aug-12	9.30
Drilling	Company			New Har	mpshire Boring	Sampling Method	2-in diam. Split Spoon		
Drilling	Foreman			Manlea \	W. Thompson	Completion Depth	32 feet bgs		
Drill Ri	g Type			CME-550)X	Surface Elevation			
Logged	l by			George N	Mavris - Weston,	Superfund Technical	Assessment and Response T	eam (STAR	Τ)
Depth (ft bgs)	Well Construct.	Split Spoon No.	Blow Counts (N)	Recovery (inches)		Soil Des	cription	Re	elative Density Descriptor
28 - 30 - 32					Split spoon soil samı	pling began at the 33 - 35	foot interval.		
34		1	WOR (12 in)-3-	11	0 - 11" Gray, CLAY,	little silt. Wet.			Soft
36		2	5-6-8-8	20	0 - 8" Gray, CLAY, 8 - 20" Gray, CLAY (little silt. Wet. (with thin laminae of brow	vn silt). Wet.		Stiff
38						-End of boring	g at 37 feet-		
W	/ell Constru	1							
		Scree Riser Filter Bento Grout Concr	sand onite seal		2-in dian Filter sar Bentonit Grout (P Concrete	neter, Schedule 40 PVC nd (0) from 25 - 32.5 ft te seal from 32.5 - 37 ar ortland Cement, Type I e (Sakrete), 0 - 1 ft bgs	nd 10 - 25 ft bgs (2 inches of sa		
		nents fr	rstem - Burmis om top of PVC ble		bgs = be	ove ground surface low ground surface ot Applicable	WOR = Weight of rods		

HRS Reference #88
Page 146 of 165
HRS Reference #54
Page 17 of 24

Westo	n Solutior	ns, Inc			SOIL BO	RING/WELL CO	MPLETION LOG	Р	age 1 of 2
Project	:			Park Stre	eet Site	Boring ID	NA	Groundwa	ter Levels*
Locatio	on			Benning	ton, Vermont	Well ID	EPA-107	Date	Depth (ft)
Date D	rilled			29-Aug-1	12	Drilling Method	ODEX and Drive and Wash	30-Aug-12	3.03
Drilling	Company			New Har	mpshire Boring	Sampling Method	2-in diam. Split Spoon		
Drilling	Foreman			Manlea '	W. Thompson	Completion Depth	22.2 feet bgs		
Drill Ri	g Type			CME-550	OX	Surface Elevation			
Logged	l by			George I	Mavris - Weston,	Superfund Technical	Assessment and Response 1	eam (STAR	Γ)
Depth (ft bgs)	Well Construct.	Split Spoon	Blow Counts (N)	Recovery (inches)		Soil Des	cription	Re	lative Density
_ 2							ders using ODEX drilling method, a	and then	-
 _ 4	$\overline{\Delta}$				ODEX casing was ren	noved and 4-inch regular	casing was advanced while using opportunity		
- 6					Water table at 3.28	feet bgs.			
8						cobbles, and boulders (w ragments), and fine-to-coa	hite, pink, tan, buff, and black qua arse sand, and silt.	ortzite and	
- 10		NA	NA	NA					NA
12 <u> </u>									
14 _									
16 <u> </u>									
18 <u></u>									
20					Split spoon soil samp	oling began at the 20 - 22	toot interval.		
- 22		1	6-11-24-28	9			GRAVEL (subangular, fines are pas tamorphic rock fragments), trace		Hard
- 24		2	14-18-22-32	12			GRAVEL (subangular, fines are pas tamorphic rock fragments), trace		Hard
					Advanced borehole	to 25 feet using drive and	wash drilling method.		

HRS Reference #88
Page 161 of 165
HRS Reference #54
Page 18 of 24

Westo	on Solution	ns, Inc			SOIL BO	RING/WELL CO	OMPLETION LOG	F	Page 2 of 2		
Project	Bennington, Vermont Well ID EPA-107 ate Drilled 29-Aug-12 Drilling Method ODEX and Drive and Wash 28-Arilling Company New Hampshire Boring Sampling Method 2-in diam. Split Spoon Completion Depth 22.2 feet bgs rilling Foreman Manlea W. Thompson Completion Depth 22.2 feet bgs rill Rig Type CME-550X Surface Elevation George Mavris - Weston, Superfund Technical Assessment and Response Team Repth Construct. Spoon No. (N) Blow Counts (N) Recovery (inches) Soil Description 26 3 17-24-35-44 20 0 - 20" Light brown and gray, SILT, some coarse-to-fine gravel (subangular), little clay (very hard, appears dry when broken). Fines plastered on gravel fragments. Wet.					Groundwa	ater Levels [*]				
Locatio	n			Benning	ton, Vermont	Well ID	EPA-107	Date	Depth (ft		
Date D	rilled			29-Aug-2	12	Drilling Method	ODEX and Drive and Wash	28-Aug-12	3.03		
Drilling	Company			New Har	mpshire Boring	Sampling Method	2-in diam. Split Spoon				
Drilling	g Foreman			Manlea '	W. Thompson	Completion Depth	22.2 feet bgs				
Logged				George I	rge Mavris - Weston, Superfund Technical Assessment and Response Team (ST						
Depth (ft bgs)		Spoon		_		Soil Des	cription	Re	elative Density Descriptor		
26		3	17-24-35-44	20	_	20" Light brown and gray, SILT, some coarse-to-fine gravel (subangular), little clay					
28									Hard		
30						-End of boring	ring at 28.5 feet-				
V	Vell Constru	iction D	etails:								
		Scree	ın.		2 in dian	notor No. 10 dot /0.01	O in Schodula 40 DVC careen	122 222 6	has		
		Riser	:11			,	0 in) Schedule 40 PVC screen, 1 Criser, 0.30 ft - 12.2 ft bgs	12.2 - 22.2 10	ngs		
		Filter	sand			nd (0) from 10 - 22.5 ft	•				
			onite seal				s (2 inches of sand on top of be	entonite) and	4		
						.5 - 25 ft bgs	5 (2 menes of same on top of se	entonice, uni	-		
		Grout	t				/II) from 1 - 3 ft bgs				
		Conci	rete		Grout (Portland Cement, Type I/II) from 1 - 3 ft bgs Concrete (Sakrete), 0 - 1 ft bgs						
	_					x (flush-mount) casing	extends to 1 ft bgs				
	Notes:										
	Soil Classifica	ation Sys	stem - Burmist	ter	ags = ab	ove ground surface	R = refusal				
	—		om top of PVC	riser	bgs = be	bgs = below ground surface					
	√ Top of v	vater ta	ble		NA = No	ot Applicable					

HRS Reference #88
Page 162 of 165
HRS Reference #54
Page 19 of 24


ATTACHMENT B – PHOTOGRAPH

PHOTODOCUMENTATION LOG Jard Company Inc Bennington, Vermont



Photograph of groundwater monitoring wells MW-3 (on left) and MW-3D (on right), located on the former building footprint portion of the Jard Company Inc. property. This photograph shows the relative similarity of the ground surface elevations at each location. Photograph taken on 2 April 2013 by Weston Solutions, Inc. personnel as part of the Site Reassessment.

ATTACHMENT C – Ground water flow elevations contour map and aerial





NOLLI

Notes:

Contour Map created using Surfer Version 8.05.

Ground water monitoring well points are labeled with Well IDs and depth to ground water elevations in feet above mean sea level.



Figure 2B

Groudwater Monitoring Well Locations

Jard Company, Inc. Bowen Road Bennington, VT

EPA Region I Superfund Technical Assessment and Response Team (START) III Contract No. EP-W-05-042

TDD Number: 12-10-0008
Created by: G. Hornok
Created on: 11 January 2013
Modified by: G. Hornok


Modified on: 13 September 2013

LEGEND

Former Building Foundation

Jard Property Boundary

Monitoring Wells



Data Sources:

Imagery: Bing Aerial Imagery

Topos: NA

All other data: START, VT ANR GIS



E:\Vt_gis\JardCoSR\MXD\Trip Report\Figure 2B-Groundwater Monitoring Wells.mxd HRS Reference #54